

GOA STATE POLLUTION CONTROL BOARD

गोंय राज्य प्रदूषण नियंत्रण मंडळ

(An ISO 9001-2015, ISO 14001:2015, ISO 45001:2018 Certified Board)

Phone Nos. : 0832-2407700
2407701, 2407702
2407703

Tel/Fax No. : 0832-2407700



Email Ids:

Chairman, GSPCB: chairman-gspcb.goa@nic.in
Member Secretary GSPCB: ms-gspcb.goa@nic.in
Office: mail.gspcb@gov.in

No. 1/27/01-PCB/Tech /144-35

Date: 9 / 11/2021

NOTICE INVITING QUOTATION

Sub: Quotation for "Electrical Point wiring with Accessories at Board laboratory cum office building at Saligao"

Sealed quotations are invited from the interested agencies by the Goa State Pollution Control Board for "Electrical Point wiring with Accessories at Board laboratory cum office building at Saligao" as per Annexure A. The contractors shall indicate the rates in figures as well as in words. The sealed cover shall be superscribed as "Electrical Point wiring with Accessories at Board laboratory cum office building at Saligao" at Board laboratory cum office building at Saligao

The contractors who are interested may inspect the site before quoting for the same. The date of submission of sealed quotations is upto **15/11/2021** at 17:00 hours and shall be opened on **17/11/2021** at 15:30 hours, in the office of Goa State Pollution Control Board and in the presence of the agencies representatives who may like to be present. The quoted rates shall be inclusive of delivery of materials/items to Goa State Pollution Control Board, etc.,

On satisfactory completion of work, final bill duly pre-receipted on revenue stamp along with copy of PAN Card shall be submitted by you to the Goa State Pollution Control Board for effecting payment.

Yours faithfully,

Member Secretary
Goa State Pollution Control Board

To,
Board's Website

Copy to:

- 1) Accounts Officer, GSPCB
- 2) Office copy

3) Guard file

ANNEXURE A : Quotation for "Electrical Point wiring with accessories in laboratory of GSPCB"

Sr. No.	Item of Work	Unit	Qty	Rate (in Figures)	Amount
POINT WIRING WITH MODULAR ACCESSORIES.					
1	Supplying and fixing suitable size modular GI box with modular plate and cover in front on surface or in recess including providing and fixing 3 pin 5/6 A modular socket outlet and 5/ 6 A modular switch connection painting etc. as required.				
a)	(a) Cat A				
2	Supplying and fixing suitable size modular GI box with modular plate and cover in front on surface or in recess including providing and fixing 6 pin 15/16 A and 5/6 A modular socket outlet modular socket outlet and 15/16 A modular switch connection painting etc. as required.	No.	16.00		
a)	(a) Cat A				
3	Supplying, installation and testing of D-Link type connector box complete with RJ-45 connector including concealed metal box/surface PVC Box, modular plate, punching, identifying, complete as required. (Includes dressing/punching in data switch)	No.	22.00		
MAINS, CIRCUITS					
4	Wiring for circuit / submain wiring alongwith earth wire with the following sizes of FR PVC insulated copper conductor single core cable in the independent surface casing capping of appropriate size as required.				
a	2 x 4 sq.mm + 1 x 2.5 sq.mm earthwire				
5	Supplying and drawing of Cat - 6 UTP, 4 pair annealed tinned copper conductor PVC insulated, PVC sheathed, unarmoured data cable in existing surface/recessed steel/PVC conduit of appropriate size including connection, etc. complete as required (a) CAT6	Metre	350.00		
6	Supply of 4 core armoured PVC insulated, PVC sheathed aluminium conductor cable of 1.1 KV grade with ISI mark conforming to IS:1554 (Part I), IS:7098 (Part II) with latest amendments of following size.	Metre	300.00		
a	4 Core 16 sq.mm				
7	Laying of one number PVC insulated and PVC sheathed/XLPE power cable of 1.1 KV grade of size not exceeding 25 sq.mm on surface, etc. complete as required	Metre	225.00		
8	Supplying and making cable end terminations with brass compression gland and aluminium lugs for following sizes of 4 Core PVC insulated PVC sheathed/XLPE aluminium conductor cable of 1.1 KV grade, complete as required.	Metre	225.00		
a	(5) 4 x 16 Sq. mm.	Each	12.00		

DISTRIBUTION BOARDS, MCB, MCCB & RCCB & PANELS					
9	Supplying and fixing following way SPN sheet steel MCB distribution board 240 V on surface/ recess complete with tinned copper busbar neutral busbar earth bar dininbar detachable gland plate interconnections phosphotized and powder painted including earthing etc. as required (but without MCB / RCCB / Isolator).	Each	4.00		
10	12 way double door Cat A	Each	25.00		
a	Supplying and fixing 6 A to 32 A, C series MCB suitable for lighting and other loads of following poles in the existing MCB DB complete with connections testing and commissioning etc as required.	Each	3.00		
11	SP, Cat A	Each	2.00		
a	Supplying and fixing 63 A, C series MCB suitable for lighting and other loads of following poles in the existing MCB DB complete with connections testing and commissioning etc as required.	Each	3.00		
12	TPN, Cat A	Each	2.00		
a	Supplying and fixing 63 A, C series MCB suitable for lighting and other loads of following poles in the existing MCB DB complete with connections testing and commissioning etc as required.	Each	3.00		
13	TP, Cat A	Each	1.00		
a	Supplying and fixing following rating double pole (single pole and neutral) 240 V RCCB having a sensitivity current upto 300mA in the existing MCB DB complete with connections testing and commissioning etc as required	Each	1.00		
14	63 A, Cat A	unit	1.00		
a	EPABX system	job	1.00		
15	Repair charges of your NEC Make EPABX system damaged due to high voltage.				
	Job work towards Onsite Maintenance along with reprogramming				
Total					
Add GST @ 12%					
Grand total					

(RUPEES