

GOA STATE POLLUTION CONTROL BOARD

गोंय राज्य प्रदूषण नियंत्रण मंडळ

(An ISO 9001-2015, ISO 14001:2015, ISO 45001:2018 Certified Board)

Phone Nos. : 0832-2407700
2407701, 2407702
2407703

Tel/Fax No. : 0832-2407700



Email Ids:

Chairman, GSPCB: chairman-gspcb.goa@nic.in
Member Secretary GSPCB: ms-gspcb.goa@nic.in
Office: mail.gspcb@gov.in

No. 1/27/01-PCB/Tech/4170

Date: 13/06/2022

NOTICE INVITING QUOTATION

Sub:Quotation for “additional AV related electrical work in conference room and 32A Power points in laboratory area at Board laboratory cum office building at Saligao”

Sealed quotations are invited from the interested agencies by the Goa State Pollution Control Board for “additional AV related electrical work in conference room and 32 A Power points in laboratory area at Board laboratory cum office building at Saligao” as per Annexure A. The contractors shall indicate the rates in figures as well as in words. The sealed cover shall be superscribed as “additional AV related electrical work in conference room and 32 A Power points in laboratory area at Board laboratory cum office building at Saligao” at Board laboratory cum office building at Saligao

The contractors who are interested may inspect the site before quoting for the same. The date of submission of sealed quotations is upto **21/06/2022** at 17:00 hours and shall be opened on **22/06/2021** at 15:30 hours, in the office of Goa State Pollution Control Board and in the presence of the agencies representatives who may like to be present. The quoted rates shall be inclusive of delivery of materials/items to Goa State Pollution Control Board. etc.,

On satisfactory completion of work, final bill duly pre-receipted on revenue stamp along with copy of PAN Card shall be submitted by you to the Goa State Pollution Control Board for effecting payment.

Yours faithfully,

(Dr. Shamila Monteiro)
Member Secretary
Goa State Pollution Control Board

To,
Board's Website

Copy to:

- 1) Accounts Officer, GSPCB
- 2) Office copy
- 3) Guard file

ANNEXURE A

Quotation for "Additional AV related electrical work in conference room and 32A Power points in laboratory of GSPCB"

Sr. No.	Item of Work	Unit	Qty	Rate (in Figures)	Amount
POINT WIRING WITH MODULAR ACCESSORIES.					
1	Supplying and fixing suitable size modular GI box with modular plate and cover in front on surface or in recess including providing and fixing 3 pin 5/6 A modular socket outlet and 5/6 A modular switch connection painting etc. as required.				
(a)	Cat A	No.	11.00		-
2	Supplying and fixing suitable size modular GI box with modular plate and cover in front on surface or in recess including providing and fixing 6 pin 15/16 A and 5/6 A modular socket outlet modular socket outlet and 15/16 A modular switch connection painting etc. as required.				
(a)	Cat A	No.	25.00		-
3	Supplying, installation and testing of D-Link type connector box complete with RJ-45 connector including concealed metal box/surface PVC box, modular plate, punching, identifying, complete as required. (Includes dressing/punching in data switch)	No.	9.00		-
4	Supplying, installation and testing of 1 module blank switch plates of Panasonic Vision make.	No.	5.00		-
5	Supplying and fixing 32 A 240 V SPN industrial type socket outlet with 2 pole and earth metal enclosed plug top along with 32 A, C series SP MCB in sheet steel enclosure in surface or in recess with chained metal cover for the socket outlet and complete with connections testing and commissioning etc. as required.				
(a)	Cat A	Each	9.00		-
MAJNS, CIRCUITS					
6	Wiring for circuit / submain wiring alongwith earth wire with the following sizes of FR PVC insulated copper conductor single core cable in the independent surface casing capping of appropriate size as required.				
(a)	2 x 4 sq.mm + 1 x 2.5 sq.mm earthwire	Metre	242.00		-
7	Supplying and drawing of Cat - 6 UTP, 4 pair annealed tinned copper conductor PVC insulated, PVC sheathed, unarmoured data cable in existing surface/recessed steel/PVC conduit of appropriate size including connection, etc. complete as required (a) CAT6	Metre	200.00		-
8	Supply of 4 core armoured PVC insulated, PVC sheathed aluminium conductor cable of 1.1 KV grade with ISI mark conforming to IS:1554 (Part I), IS:7098 (Part II) with latest amendments of following size.				
(a)	4 Core 50 sq.mm	Metre	106.00		-
9	Laying of one number PVC insulated and PVC sheathed/XLPE power cable of 1.1 KV grade of size more than 25 sq. mm not exceeding 120 sq.mm on surface, etc. complete as required	Metre	106.00		-
10	Supplying and making cable end terminations with brass compression gland and aluminium lugs for following sizes of 4 Core PVC insulated PVC sheathed/XLPE aluminium conductor cable of 1.1 KV grade, complete as required.				
(a)	4 x 50 Sq. mm.	Each	2.00		-
DISTRIBUTION BOARDS, MCB					
11	Supplying and fixing following way TPN sheet steel MCB distribution board 440 V on surface/ recess complete with finned copper busbar neutral busbar earth bar dinnbar detachable gland plate interconnections phosphotized and powder painted including earthing etc. as required (but without MCB / RCCB / Isolator).				
(a)	4 way double door Cat A	Each	1.00		-
12	Supplying and fixing 6 A to 32 A, C series MCB suitable for lighting and other loads of following poles in the existing MCB DB complete with connections testing and commissioning etc as required.				
(a)	SP, Cat A	Each	12.00		-
13	Supplying and fixing 63 A, C series MCB suitable for lighting and other loads of following poles in the existing MCB DB complete with connections testing and commissioning etc as required.				
(a)	TPN, Cat A	Each	1.00		-
14	Supplying and fixing of 8 way unmanaged POE switch	Each	1.00		-
15	Supplying and fixing of 4 channel raceway for floor cable management	Metre	30.00		-
16	Supplying and fixing of following sizes of PVC conduit alongwith accessories in surface/recess including cutting the wall and making good the same in case of recessed conduit as required.				
(a)	25 mm	Metre	30.00		-
(b)	32 mm	Metre	6.00		-
Total					
Add GST @ 18%					
Grand total					